

Development Consent

Section 4.38 of the Environmental Planning and Assessment Act 1979

As delegate of the Minister for Planning and Public Spaces under delegation executed on 9 March 2022, I approve the Development Application referred to in Schedule 1, subject to the conditions specified in Schedule 2.

These conditions are required to:

- prevent, minimise, or offset adverse environmental impacts;
- set standards and performance measures for acceptable environmental performance;
- require regular monitoring and reporting; and
- provide for the ongoing environmental management of the development.



Karen Harragon
Director
Social Infrastructure Assessments

Sydney

17 December 2025

SCHEDULE 1

Application Number:	SSD-57838709
Applicant:	The University of Sydney
Consent Authority:	Minister for Planning and Public Spaces
Site:	The University of Sydney, Parramatta Road, Camperdown (Lot 101 in DP 1270568)
Development:	Construction of a new five level multi-disciplinary general teaching space building.

DEFINITIONS

Aboriginal object	Has the same meaning as the definition of the term in section 5 of the <i>National Parks and Wildlife Act 1974</i>
Aboriginal place	Has the same meaning as the definition of the term in section 5 of the <i>National Parks and Wildlife Act 1974</i>
Accredited Certifier	Means the holder of accreditation as an accredited certifier under the <i>Building Professionals Act 2005</i> acting in relation to matters to which the accreditation applies.
Advisory Notes	Advisory information relating to the consent but do not form a part of this consent
Applicant	The University of Sydney or any other person carrying out any development to which this consent applies
Approved disturbance area	The area identified as such on the development layout
BCA	Building Code of Australia
BC Act	<i>Biodiversity Conservation Act 2016</i>
BCD	Biodiversity and Conservation Division of the NSW Department of Climate Change, Energy, the Environment and Water
CEMP	Construction Environmental Management Plan
Certification of Crown building work	Certification under section 6.28(2) of the EP&A Act
Certified Contaminated Land Consultant	A person certified in accordance with the requirements of the Contaminated Land Consultant Certification Policy Version 2 (EPA November 2017) or any subsequent policies as in force from time to time
Certifier	Means a council or accredited certifier or in the case of Crown development, a person qualified to conduct a Certification of Crown Building work
Conditions of this consent	The conditions contained in Schedule 2 of this document
Construction	All physical work to enable operation including (unless specifically excluded by a condition) but not limited to the demolition and removal of buildings, the carrying out of works for the purposes of the development, including bulk earthworks, and erection of buildings and other infrastructure permitted by this consent, but excluding the following: • building and road dilapidation surveys; • investigative drilling or investigative excavation; • Archaeological Salvage; • establishing temporary site offices (in locations identified by the conditions of this consent); • installation of environmental impact mitigation measures, fencing, enabling works; and • minor adjustments to services or utilities However, where heritage items, or threatened species or threatened ecological communities (within the meaning of the <i>Biodiversity Conservation Act 2016</i> are affected or potentially affected by any physical work, that work is construction, unless otherwise determined by the Planning Secretary in consultation with relevant NSW government agencies
Council	City of Sydney
Day	The period from 7am to 6pm on Monday to Saturday, and 8am to 6pm on Sundays and Public Holidays
Demolition	The deconstruction and removal of buildings, sheds and other structures on the site

Department	NSW Department of Planning, Housing and Infrastructure
Development	The development described in the EIS and Response to Submissions, including the works and activities comprising construction of tertiary facilities, as modified by the conditions of this consent
DIP	Design Integrity Panel
Earthworks	Bulk earthworks, site levelling, import and compaction of fill material, excavation for installation of drainage and services
EIS	The Environmental Impact Statement titled A01 Ross Street Teaching and Learning Hub, prepared by MG Planning dated February 2025, submitted with the application for consent for the development, including any additional information provided by the Applicant in support of the application
ENM	Excavated Natural Material
Environment	Includes all aspects of the surroundings of humans, whether affecting any human as an individual or in his or her social groupings
EPA	NSW Environment Protection Authority
EP&A Act	<i>Environmental Planning and Assessment Act 1979</i>
EP&A Regulation	Environmental Planning and Assessment Regulation 2021
Evening	The period from 6pm to 10pm
Feasible	Means what is possible and practical in the circumstances
Heritage	Encompasses both Aboriginal and historic heritage including sites that predate European settlement, and a shared history since European settlement
Heritage NSW	Heritage NSW, the NSW Department of Climate Change, Energy, the Environment and Water
Heritage Item	An item as defined under the <i>Heritage Act 1977</i> , and assessed as being of local, State and/ or National heritage significance, and/or an Aboriginal Object or Aboriginal Place as defined under the <i>National Parks and Wildlife Act 1974</i> , the World Heritage List, or the National Heritage List or Commonwealth Heritage List under the <i>Environment Protection and Biodiversity Conservation Act 1999</i> (Cth), or anything identified as a heritage item under the conditions of this consent
Incident	An occurrence or set of circumstances that causes, or threatens to cause, material harm and which may or may not be, or cause, a non-compliance <i>Note: "material harm" is defined in this consent</i>
Independent Audit Post Approval Requirements	Independent Audit Post Approval Requirements 2020 (or other updated version as available on the Department's website)
Land	Has the same meaning as the definition of the term in section 1.4 of the EP&A Act
EMP	Environmental Management Plan
Management and mitigation measures	The management and mitigation measures set out in Appendix R of the Response to Submissions.
Material harm	Is harm that: a) involves actual or potential harm to the health or safety of human beings or to the environment that is not trivial; or b) results in actual or potential loss or property damage of an amount, or amounts in aggregate, exceeding \$10,000, (such loss includes the reasonable costs and expenses that would be incurred in taking all reasonable and practicable measures to prevent, mitigate or make good harm to the environment) <i>Note: For the purposes of this definition, material harm excludes incidents captured by Work Health and Safety reporting requirements.</i>

Minister	NSW Minister for Planning and Public Spaces (or delegate)
Mitigation	Activities associated with reducing the impacts of the development prior to or during those impacts occurring
Monitoring	Any monitoring required under this consent must be undertaken in accordance with section 9.39 of the EP&A Act
Night	The period from 10pm to 7am on Monday to Saturday, and 10pm to 8am on Sundays and Public Holidays
Non-compliance	An occurrence, set of circumstances or development that is a breach of this consent
Operation	The carrying out of the approved purpose of the development upon completion of construction
PA	Means a planning agreement within the meaning of the term in section 7.4 of the EP&A Act
Planning Secretary	Planning Secretary under the EP&A Act, or nominee
POEO Act	<i>Protection of the Environment Operations Act 1997</i>
Reasonable	Means applying judgement in arriving at a decision, taking into account: mitigation, benefits, costs of mitigation versus benefits provided, community views, and the nature and extent of potential improvements
Registered Aboriginal Parties	Means the Aboriginal persons identified in accordance with the document entitled “ <i>Aboriginal cultural heritage consultation requirements for proponents 2010</i> ” (DECCW)
Rehabilitation	The restoration of land disturbed by the development to a good condition, to ensure it is safe, stable and non-polluting
Response to submissions	The Applicant’s response to issues raised in submissions received in relation to the application for consent for the development under the EP&A Act
Sensitive receivers	A location where people are likely to work, occupy or reside, including a dwelling, school, hospital, office or public recreational area
Site	The land defined in Schedule 1
Site Auditor	As defined in section 4 of the <i>Contaminated Land Management Act 1997</i>
Site Audit Report	As defined in section 4 of the <i>Contaminated Land Management Act 1997</i>
Site Audit Statement	As defined in section 4 of the <i>Contaminated Land Management Act 1997</i>
TfNSW	Transport for New South Wales
VENM	Virgin Excavated Natural Material
Waste	Has the same meaning as the definition of the term in the Dictionary to the POEO Act
Year	A period of 12 consecutive months

SCHEDULE 2

PART A ADMINISTRATIVE CONDITIONS

Obligation to Minimise Harm to the Environment

- A1. In addition to meeting the specific performance measures and criteria in this consent, all reasonable and feasible measures must be implemented to prevent, and, if prevention is not reasonable and feasible, minimise any material harm to the environment that may result from the construction and operation of the development.

Terms of Consent

- A2. The development may only be carried out:
- (a) in compliance with the conditions of this consent;
 - (b) in accordance with all written directions of the Planning Secretary;
 - (c) generally in accordance with the EIS and Response to Submissions;
 - (d) in accordance with the approved plans in the table below:

Architectural drawings prepared by <i>BNV</i>			
Dwg No.	Rev	Name of Plan	Date
AR-02A-XX-01	08	Cover Sheet	21/01/2025
AR-02A-XX-03	06	Demolition Plan	12/08/2025
AR-02A-XX-04	07	Proposed Site Plan	16/10/2024
AR-02A-XX-10	06	Proposed Site Elevations	16/10/2024
AR-02B-01-02	08	General Arrangement Plan – Level 01	16/01/2025
AR-02B-02-02	09	General Arrangement Plan – Level 02	24/07/2025
AR-02B-03-02	08	General Arrangement Plan – Level 03	16/01/2025
AR-02B-04-02	08	General Arrangement Plan – Level 04	16/01/2025
AR-02B-05-02	08	General Arrangement Plan – Level 05	16/01/2025
AR-02B-06-02	09	General Arrangement Plan – Roof	22/01/2025
AR-02C-XX-01	04	North Elevation	16/10/2024
AR-02C-XX-02	04	West Elevation	16/10/2024
AR-02C-XX-03	07	South Elevation	16/10/2024
AR-02C-XX-04	07	East Elevation	16/10/2024
AR-02D-XX-01	08	Sections	16/01/2025
AR-02D-XX-02	08	Sections	16/01/2025
AR-02D-XX-03	05	Sections	16/01/2025
AR-02D-XX-04	01	Sections	16/01/2025
AR-02D-XX-05	01	Sections	22/01/2025
AR-02Y-XX-02	06	Schedule of Finishes	16/10/2024
Landscape drawings prepared by <i>Oculus</i>			
Dwg No.	Rev	Name of Plan	Date
SSDA00	5	Cover Sheet	06/08/2025
SSDA01	5	Legend Sheet	06/08/2025
SSDA03	5	Planting Schedule	06/08/2025
SSDA10	7	Tree Retention and Removal Plan	06/08/2025
SSDA11	3	Demolition Plan	06/08/2025
SSDA20	6	Surface Finishes Level 02	06/08/2025

SSDA30	6	Levels Plan Level 02	06/08/2025
SSDA40	1	Soil Volume Plan Level 02	06/08/2025
SSDA50	6	Planting Plan Level 02	06/08/2025
SSDA51	3	Planting Plan Level 01 + 03	06/08/2025
SSDA52	1	Planting Plan Level 04 + 05	06/08/2025
SSDA70	5	Sections	06/08/2025
SSDA71	5	Sections	06/08/2025

- A3. The Applicant must comply with all written requirements or directions of the Planning Secretary, including in relation to:
- (a) the environmental performance of the approved development;
 - (b) any document or correspondence in relation to the approved development;
 - (c) any notification given to the Planning Secretary under the terms of this approval;
 - (d) any audit of the construction or operation of the construction or operation of the approved development;
 - (e) the terms of this approval and compliance with the terms of the approval (including anything required to be done under the approval);
 - (f) the carrying out of any additional monitoring and management measures; and
 - (g) in respect of ongoing monitoring and management obligations, compliance with an updated or revised version of a guideline, protocol, Australian Standard or policy required to be complied with under this approval.
- A4. Consistent with the requirements in this consent, the Planning Secretary may make written directions to the Applicant in relation to:
- (a) the content of any strategy, study, system, plan, program, review, audit, notification, report or correspondence submitted under or otherwise made in relation to this consent, including those that are required to be, and have been, approved by the Planning Secretary;
 - (b) any reports, reviews or audits commissioned by the Planning Secretary regarding compliance with this approval; and
 - (c) the implementation of any actions or measures contained in any such document referred to in (a) above.
- A5. The conditions of this consent and directions of the Planning Secretary prevail to the extent of any inconsistency, ambiguity or conflict between them and a document listed in condition A2(c). In the event of an inconsistency, ambiguity or conflict between any of the documents listed in condition A2(c), the most recent document prevails to the extent of the inconsistency, ambiguity or conflict.

Limits of Consent

- A6. This consent lapses five years after the date of consent unless work is physically commenced.

Prescribed Conditions

- A7. The Applicant must comply with all relevant conditions of development consent under Part 4, Division 2, Subdivision 1 of the EP&A Regulation.

Planning Secretary as Moderator

- A8. In the event of a dispute between the Applicant and a public authority, in relation to an applicable requirement in this approval or relevant matter relating to the Development, either party may refer the matter to the Planning Secretary for resolution. The Planning Secretary's resolution of the matter must be binding on the parties.

Evidence of Consultation

- A9. Where conditions of this consent require consultation with an identified party, the Applicant must:
- (a) consult with the relevant party prior to submitting the subject document for information or approval; and
 - (b) provide details of the consultation undertaken including:
 - (i) the outcome of that consultation, matters resolved and unresolved; and
 - (ii) details of any disagreement remaining between the party consulted and the Applicant and how the Applicant has addressed the matters not resolved.

Staging

- A10. The project may be constructed and operated in stages. Where compliance with conditions is required to be staged due to staged construction or operation, a Staging Report (for either or both construction and operation as the case may be) must be prepared and submitted to the Planning Secretary for approval. The Staging Report must be submitted to the Planning Secretary no later than one month before the commencement of construction of the first of the proposed stages of construction (or if only staged operation is proposed, one month before the commencement of operation of the first of the proposed stages of operation).
- A11. A Staging Report prepared in accordance with condition A10 must:
- (a) if staged construction is proposed, set out how the construction of the whole of the project will be staged, including details of work and other activities to be carried out in each stage and the general timing of when construction of each stage will commence and finish;
 - (b) if staged operation is proposed, set out how the operation of the whole of the project will be staged, including details of work and other activities to be carried out in each stage and the general timing of when operation of each stage will commence and finish (if relevant);
 - (c) specify how compliance with conditions will be achieved across and between each of the stages of the project;
 - (d) specify how compliance with independent auditing requirements will be achieved across and between each of the operational stages of the project; and
 - (e) set out mechanisms for managing any cumulative impacts arising from the proposed staging.
- A12. Where a Staging Report is required, the project must be staged in accordance with the Staging Report, as approved by the Planning Secretary.
- A13. Where construction or operation is being staged in accordance with a Staging Report, the terms of this consent that apply or are relevant to the works or activities to be carried out in a specific stage must be complied with at the relevant time for that stage as identified in the Staging Report including independent auditing requirements.

Staging, Combining and Updating Strategies, Plans or Programs

- A14. The Applicant may:
- (a) prepare and submit any strategy, plan (including management plan, architectural or design plan) or program required by this consent on a staged basis (if a clear description is provided as to the specific stage and scope of the development to which the strategy, plan (including management plan, architectural or design plan) or program applies, the relationship of the stage to any future stages and the trigger for updating the strategy, plan (including management plan, architectural or design plan) or program);
 - (b) combine any strategy, plan (including management plan, architectural or design plan), or program required by this consent (if a clear relationship is demonstrated between the strategies, plans (including management plan, architectural or design plan) or programs that are proposed to be combined); and
 - (c) update any strategy, plan (including management plan, architectural or design plan), or program required by this consent (to ensure the strategies, plans (including management

plan, architectural or design plan), or programs required under this consent are updated on a regular basis and incorporate additional measures or amendments to improve the environmental performance of the development).

- A15. Any strategy, plan or program prepared in accordance with condition A14, where previously approved by the Planning Secretary under this consent, must be submitted to the satisfaction of the Planning Secretary.
- A16. If the Planning Secretary agrees, a strategy, plan (including management plan, architectural or design plan), or program may be staged or updated without consultation being undertaken with all parties required to be consulted in the relevant condition in this consent.
- A17. Updated strategies, plans (including management plan, architectural or design plan), or programs supersede the previous versions of them and must be implemented in accordance with the condition that requires the strategy, plan, program or drawing.

Structural Adequacy

- A18. All new buildings and structures, and any alterations or additions to existing buildings and structures, that are part of the development, must be constructed in accordance with the relevant requirements of the BCA.

Notes:

- *Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021 sets out the requirements for the certification of the development.*

External Walls and Cladding

- A19. The external walls of all buildings including additions to existing buildings must comply with the relevant requirements of the BCA.

Applicability of Guidelines

- A20. References in the conditions of this consent to any guideline, protocol, Australian Standard or policy are to such guidelines, protocols, Standards or policies in the form they are in as at the date of this consent.
- A21. Consistent with the conditions of this consent and without altering any limits or criteria in this consent, the Planning Secretary may, when issuing directions under this consent in respect of ongoing monitoring and management obligations, require compliance with an updated or revised version of such a guideline, protocol, Standard or policy, or a replacement of them.

Monitoring and Environmental Audits

- A22. Any condition of this consent that requires the carrying out of monitoring or an environmental audit, whether directly or by way of a plan, strategy or program, is taken to be a condition requiring monitoring or an environmental audit under Division 9.4 of Part 9 of the EP&A Act. This includes conditions in respect of incident notification, reporting and response, non-compliance notification, Site audit report and independent auditing.

Note: For the purposes of this condition, as set out in the EP&A Act, "monitoring" is monitoring of the development to provide data on compliance with the consent or on the environmental impact of the development, and an "environmental audit" is a periodic or particular documented evaluation of the development to provide information on compliance with the consent or the environmental management or impact of the development.

Access to Information

- A23. At least 48 hours before the commencement of construction until the completion of all works under this consent, or such other time as agreed by the Planning Secretary, the Applicant must:
- (a) make the following information and documents (as they are obtained or approved) publicly available on its website:
- (i) the documents referred to in condition A2 of this consent;
 - (ii) all current statutory approvals for the development;
 - (iii) all approved strategies, plans and programs required under the conditions of this consent;

- (iv) regular reporting on the environmental performance of the development in accordance with the reporting arrangements in any plans or programs approved under the conditions of this consent;
 - (v) a comprehensive summary of the monitoring results of the development, reported in accordance with the specifications in any conditions of this consent, or any approved plans and programs;
 - (vi) a summary of the current stage and progress of the development;
 - (vii) contact details to enquire about the development or to make a complaint;
 - (viii) a complaints register, updated monthly;
 - (ix) audit reports prepared as part of any independent audit of the development and the Applicant's response to the recommendations in any audit report;
 - (x) any other matter required by the Planning Secretary; and
- (b) keep such information up to date, to the satisfaction of the Planning Secretary and publicly available for 12 months after the commencement of operations.

Compliance

- A24. The Applicant must ensure that all of its employees, contractors (and their sub-contractors) are made aware of, and are instructed to comply with, the conditions of this consent relevant to activities they carry out in respect of the development.

Incident Notification, Reporting and Response

- A25. The Planning Secretary must be notified through the major projects portal immediately after the Applicant becomes aware of an incident. The notification must identify the development (including the development application number and the name of the development if it has one) and set out the location and nature of the incident.
- A26. Subsequent notification must be given and reports submitted in accordance with the requirements set out in **Appendix 2**.

Non-Compliance Notification

- A27. The Planning Secretary must be notified through the major projects portal within seven days after the Applicant becomes aware of any non-compliance.
- A28. The notification must identify the development and the application number for it, set out the condition of consent that the development is non-compliant with, the way in which it does not comply and the reasons for the non-compliance (if known) and what actions have been, or will be, undertaken to address the non-compliance.
- A29. A non-compliance which has been notified as an incident does not need to also be notified as a non-compliance.

Revision of Strategies, Plans and Programs

- A30. Within three months of:
- (a) the submission of an incident report under condition A26;
 - (b) the submission of an Independent Audit under condition C43;
 - (c) the approval of any modification of the conditions of this consent; or
 - (d) the issue of a direction of the Planning Secretary under condition A3 which requires a review,
- the strategies, plans and programs required under this consent must be reviewed, and the Planning Secretary and the Certifier must be notified in writing that a review is being carried out.
- A31. If necessary to either improve the environmental performance of the development, cater for a modification or comply with a direction, the strategies, plans, programs or drawings required under this consent must be revised, to the satisfaction of the Planning Secretary or Certifier (where previously approved by the Certifier). Where revisions are required, the revised document must be submitted to the Planning Secretary and / or Certifier for approval and / or information (where relevant) within six weeks of the review.

Note: This is to ensure strategies, plans and programs are updated on a regular basis and to incorporate any recommended measures to improve the environmental performance of the development.

PART B PRIOR TO COMMENCEMENT OF CONSTRUCTION

Notification of Commencement

- B1. The Applicant must notify the Planning Secretary in writing of the dates of the intended commencement of construction and operation at least 48 hours before those dates.
- B2. If the construction or operation of the development is to be staged, the Planning Secretary must be notified in writing at least 48 hours before the commencement of each stage, of the date of commencement and the development to be carried out in that stage.

Certified Drawings

- B3. Prior to the commencement of construction, the Applicant must submit to the Certifier structural drawings prepared and signed by a suitably qualified practising Structural Engineer that demonstrates compliance with this development consent.

External Walls and Cladding

- B4. Prior to the commencement of construction, the Applicant must provide the Certifier with documented evidence that the products and systems proposed for use or used in the construction of external walls, including finishes and claddings such as synthetic or aluminium composite panels, comply with the requirements of the BCA. A copy of the documentation must be made available on the Applicant's website within seven days after the Certifier accepts it.

Pre-Construction Dilapidation Report – Protection of Public Infrastructure

- B5. Prior to the commencement of construction, the Applicant must:
 - (a) consult with the relevant owner and provider of services and Infrastructure that are likely to be affected by the development to make suitable arrangements for access to, diversion, protection and support of the affected infrastructure;
 - (b) prepare a Pre-Construction Dilapidation Report identifying the condition of all public (non-residential) infrastructure and assets in the vicinity of the site (including roads, gutters and footpaths) that have potential to be affected;
 - (c) submit a copy of the Pre-Construction Dilapidation Report to the asset owner, Certifier and Council; and
 - (d) provide a copy of the Pre-Construction Dilapidation Report to the Planning Secretary with 48 hours when requested.

Ecologically Sustainable Development

- B6. Prior to the commencement of construction, unless otherwise agreed by the Planning Secretary, the Applicant must demonstrate that ESD is being achieved by either:
 - (a) registering for a minimum 5 star Green Star rating with the Green Building Council Australia and submit evidence of registration to the Certifier; or
 - (b) seeking approval from the Planning Secretary for an alternative certification process.

Outdoor Lighting

- B7. Prior to commencement of lighting installation, evidence must be submitted to the Certifier that all outdoor lighting to be installed within the site has been designed to comply with AS 1158.3.1:2005 Lighting for roads and public spaces – Pedestrian area (Category P) lighting – Performance and design requirements and AS 4282-2019 Control of the obtrusive effects of outdoor lighting.

Demolition

- B8. Prior to the commencement of construction, demolition work plans required by AS 2601-2001 *The demolition of structures* (Standards Australia, 2001) must be accompanied by a written statement from a suitably qualified person that the proposals contained in the work plan comply with the safety requirements of the Standard. The work plans and the statement of compliance must be submitted to the Certifier.

Environmental Management Plan Requirements

- B9. Management plans required under this consent must be prepared having regard to the relevant guidelines, including but not limited to the *Environmental Management Plan Guideline: Guideline for Infrastructure Projects* (DPIE April 2020).

Notes:

- The *Environmental Management Plan Guideline* is available on the Planning Portal at: <https://www.planningportal.nsw.gov.au/major-projects/assessment/post-approval>
- The Planning Secretary may waive some of these requirements if they are unnecessary or unwarranted for particular management plans.

Construction Environmental Management Plan

- B10. Prior to the commencement of any construction, the Applicant must submit a Construction Environmental Management Plan (CEMP) to the Certifier and publish a copy of the CEMP on the Applicant's website in accordance with condition A23 (Access to Information). The CEMP must include, but not be limited to, the following:

- (a) Details of:
- (i) hours of work;
 - (ii) 24-hour contact details of site manager;
 - (iii) management of dust and odour to protect the amenity of the neighbourhood;
 - (iv) stormwater control and discharge;
 - (v) measures to ensure that sediment and other materials are not tracked onto the roadway by vehicles leaving the site;
 - (vi) groundwater management plan including measures to prevent groundwater contamination;
 - (vii) external lighting in compliance with AS 4282-2019 Control of the obtrusive effects of outdoor lighting;
- (b) an unexpected finds protocol for contamination and associated communications procedure to ensure that potentially contaminated material is appropriately managed;
- (c) an unexpected finds protocol for Aboriginal and non-Aboriginal heritage and associated communications procedure;
- (d) Construction Traffic and Pedestrian Management Sub-Plan (see condition B11);
- (e) Construction Noise and Vibration Management Sub-Plan (see condition B12);
- (f) Construction Waste Management Sub-Plan (see condition B13); and
- (g) Construction Flood Emergency Management Plan (see condition B14).

- B11. The Construction Traffic and Pedestrian Management Sub-Plan (CTPMSP) must be prepared to achieve the objective of ensuring safety and efficiency of the road network and address, but not be limited to, the following:

- (a) be prepared by a suitably qualified and experienced person(s);
- (b) be prepared in consultation with Council and TfNSW;
- (c) detail:
- (i) measures to ensure road safety and network efficiency during construction in consideration of potential impacts on general traffic, cyclists and pedestrians and bus services;
 - (ii) measures to ensure the safety of vehicles and pedestrians accessing adjoining properties where shared vehicle and pedestrian access occurs;
 - (iii) heavy vehicle routes, access and parking arrangements;
 - (iv) the swept path of the longest construction vehicle entering and exiting the site in association with the new work, as well as manoeuvrability through the site, in accordance with the latest version of AS 2890.2; and
 - (v) arrangements to ensure that construction vehicles enter and leave the site in a forward direction unless in specific exceptional circumstances under the supervision of accredited traffic controller(s).

- B12. The Construction Noise and Vibration Management Sub-Plan must address, but not be limited to, the following:
- (a) be prepared by a suitably qualified and experienced noise expert;
 - (b) describe procedures for achieving the noise management levels in EPA's *Interim Construction Noise Guideline* (DECC, 2009);
 - (c) describe the measures to be implemented to manage high noise generating works such as piling, in close proximity to sensitive receivers;
 - (d) include strategies that have been developed with the community for managing high noise generating works;
 - (e) include a complaints management system that would be implemented for the duration of the construction; and
 - (f) include a program to monitor and report on the impacts and environmental performance of the development and the effectiveness of the implemented management measures in accordance with the requirements of condition B23.
- B13. The Construction Waste Management Sub-Plan (CWMSP) must address, but not be limited to, the procedures for the management of waste including the following:
- (a) the recording of quantities, classification (for materials to be removed) and validation (for materials to remain) of each type of waste generated during construction and proposed use for materials to remain;
 - (b) information regarding the recycling and disposal locations; and
 - (c) confirmation of the contamination status of the development areas of the site based on the validation results.
- B14. The Construction Flood Emergency Management Sub-Plan must address, but not be limited to, the following:
- (a) be prepared by a suitably qualified and experienced person(s);
 - (b) address the provisions of the *Floodplain Risk Management Guidelines*;
 - (c) include details of:
 - (i) the flood emergency responses for both construction phases of the development;
 - (ii) predicted flood levels;
 - (iii) flood warning time and flood notification;
 - (iv) assembly points and evacuation routes;
 - (v) evacuation and refuge protocols; and
 - (vi) awareness training for employees and contractors, and users/visitors.
- B15. A Driver Code of Conduct must be prepared and communicated by the Applicant to heavy vehicle drivers and must address the following:
- (a) minimise the impacts of earthworks and construction on the local and regional road network;
 - (b) minimise conflicts with other road users;
 - (c) minimise road traffic noise; and
 - (d) ensure truck drivers use specified routes.

Construction Parking

- B16. Prior to the commencement of any construction, the Applicant must provide sufficient parking facilities on-campus, including for heavy vehicles, to ensure that construction traffic associated with the development does not utilise public and residential streets or public parking facilities.
- B17. Prior to the commencement of any construction, the Applicant must submit a Construction Worker Transportation Strategy to the Certifier. The Strategy must detail the provision of sufficient parking facilities or other travel arrangements for construction workers in order to minimise demand for parking in nearby public and residential streets or public parking facilities.

A copy of the strategy must be published on the Applicant's website in accordance with condition A23. This condition cannot be staged.

Soil and Water

- B18. Prior to the commencement of construction, the Applicant must:
- (a) install erosion and sediment controls on the site to manage wet weather events; and
 - (b) divert existing clean surface water around operational areas of the site.
- B19. Prior to the commencement of construction, erosion and sediment controls must be installed and maintained, as a minimum, in accordance with the publication *Managing Urban Stormwater: Soils & Construction* (4th edition, Landcom 2004) commonly referred to as the 'Blue Book'.

Flood Management

- B20. Prior to the commencement of construction, the Applicant must prepare and implement for the duration of construction:
- (a) flood warning and notification procedures for construction workers on site; and
 - (b) evacuation and refuge protocols.
- B21. Prior to the commencement of construction, details must be provided to the Certifier confirming that any structures below the 1% Annual Exceedance Probability plus 500mm of freeboard are constructed from flood compatible building components.
- B22. Prior to the commencement of construction, the Applicant must provide evidence from a suitably qualified civil or structural engineer to the Certifier confirming that the structural integrity of the building has been designed to withstand the 1% Annual Exceedance Probability flood.

Operational Noise – Design of Mechanical Plant and Equipment

- B23. Prior to installation of mechanical plant and equipment:
- (a) a detailed assessment of mechanical plant and equipment with compliance with the relevant project noise trigger levels as recommended in the *SSDA Noise and Vibration Impact Assessment* dated 3/09/2024 and prepared by Acoustic Logic must be undertaken by a suitably qualified person; and
 - (b) evidence must be submitted to the Certifier that any noise mitigation recommendations identified in the assessment carried out under (a) have been incorporated into the design to ensure the development will not exceed the project noise trigger levels as identified in the *SSDA Noise and Vibration Impact Assessment* and prepared by Acoustic Logic.

Construction and Demolition Waste Management

- B24. Prior to the commencement of the removal of any waste material from the site, the Applicant must notify the TfNSW Traffic Management Centre of the truck route(s) to be followed by trucks transporting waste material from the site.

Operational Waste Storage and Processing

- B25. Prior to the commencement of construction of waste storage and processing areas, the Applicant must obtain agreement from Council for the design of the operational waste storage area (where waste removal will be undertaken by Council). Where waste removal will be undertaken by a third party, evidence must be provided to the Certifier that the design of the operational waste storage area:
- (a) is constructed using solid non-combustible materials;
 - (b) is designed to ensure the door/gate to the waste storage area is vermin proof and can be openable from both inside and outside the storage area at all times;
 - (c) includes a hot and cold water supply with a hose through a centralised mixing valve;
 - (d) is naturally ventilated or an air handling exhaust system must be in place; and
 - (e) includes signage to clearly describe the types of materials that can be deposited into recycling bins and general garbage bins.

Operational Access and Service Vehicle Arrangements

- B26. Prior to the commencement of construction of operational parking and access facilities, evidence of compliance of the design of operational parking and access arrangements with the following requirements must be submitted to the Certifier:
- (a) a minimum of one on-site space for servicing and waste during operation of the development and designed in accordance with the relevant Australian Standards; and
 - (b) the swept path of the largest service vehicle entering and exiting the Site in association with the new work, as well as manoeuvrability through the site, must be in accordance with the latest version of AS 2890.2.

Public Domain Works

- B27. Prior to the commencement of any footpath or public domain works on Council land, the Applicant must consult with Council and demonstrate to the Certifier that the streetscape design and treatment meets the requirements of Council, including addressing pedestrian management. The Applicant must submit documentation of approval for each stage from Council to the Certifier.

Heritage

- B28. The final design of details of the Ross Street Gates sandstone columns and palisade fence, including the design of columns flagging new openings to the palisade fence, are to be provided to the Planning Secretary for approval, including evidence of support from Heritage NSW for the final design.
- B29. All works to the Ross Street Gates sandstone columns and palisade fence are to be undertaken by suitably qualified and experienced tradespersons.
- B30. A revised Heritage Interpretation Plan (HIP) must be prepared in consultation with Heritage NSW and submitted to the Certifier and Planning Secretary prior to the commencement of landscaping works on site. The revised HIP is to include detailed designs for the interpretation media, and consideration of interpretation of historical archaeology on the site (if identified).
- B31. Archaeological monitoring is required to identify and record potential features associated with World War II air raid trenches. An Archaeological Work Method Statement (AWMS) is to be completed for the project in accordance with the guideline Archaeological assessment (Heritage Office and DUAP 1996) and in consultation with Heritage NSW, to inform and guide archaeological investigations. The AWMS must:
- (a) identify the potential archaeological resource on site, and how it will be impacted by the proposed works;
 - (b) identify research questions to guide the archaeological program;
 - (c) propose a methodology for archaeological monitoring on site;
 - (d) provide an Unexpected Finds Procedure for the proposed works;
 - (e) provide a methodology for post-excavation analysis and reporting; and
 - (f) be provided to the Certifier and the Planning Secretary prior to the commencement of construction.
- B32. If required by condition B31(e), a Final Excavation Report is to be prepared and provided to Heritage NSW within 12 months of the completion of archaeological investigations for accession to the Heritage Library.
- B33. Prior to commencement of construction, the following documents are to be prepared and provided to the Certifier for the Ross Street Gates sandstone columns and palisade fence by a suitably qualified and experienced heritage consultant:
- (a) a Schedule of Conservation Works for the Ross Street Gates sandstone pillars, to be implemented as part of the approved works; and
 - (b) a Salvage Methodology for the portions of palisade fence, stone base, and c.1910 metal gate approved for removal. This Salvage Methodology should clearly outline the steps for safe removal of the materials and storage for future use.

- B34. A photographic archival of the Ross Street Gates and palisade fence (including stone base and c.1910 metal gate) must be prepared prior to the commencement of construction. This recording must be prepared in accordance with the Heritage NSW publication *Guidelines for preparing archival recordings of heritage items as a condition of consent* (DECCW 2025). The digital copy of the archival record must be submitted electronically to Heritage NSW. The relevant format and specifications of the record are published on the Heritage NSW website.

Aboriginal Cultural Heritage

- B35. Prior to the commencement of construction, the Applicant must ensure Aboriginal heritage management procedures are prepared for the development and included in the Project's Construction Environmental Management Plan (CEMP). The Aboriginal heritage management procedures must:
- (a) be prepared by suitably qualified and experienced persons.
 - (b) be prepared in consultation with Registered Aboriginal Parties and be reviewed by Heritage NSW.
 - (c) include a description of the measures that would be implemented for:
 - i. ongoing consultation with Registered Aboriginal Parties, including consultation regarding changes to the management of Aboriginal cultural heritage.
 - ii. a contingency plan and reporting procedure for the management of Unexpected Heritage Finds and Human Remains that is prepared by suitably qualified and experienced heritage specialist in relation to Aboriginal cultural heritage, in consultation with the Registered Aboriginal Parties and in accordance with the *Code of practice for archaeological investigation of Aboriginal objects in New South Wales* (DECCW 2010). The Unexpected Heritage Finds and Human Remains Procedure, as submitted to the Planning Secretary, must be implemented for the duration of construction.
 - iii. ensuring workers on site receive suitable heritage inductions prior to carrying out any development on site, and that records are kept of these inductions.

TfNSW – Bike Box

- B36. The minimum driver sight line distances from the northbound approach on Western Avenue to pedestrians on the southern footway of Parramatta Road must comply with the relevant Austroads guidelines. Vegetation within University grounds is to be removed as necessary to ensure compliant driver visibility is achieved and maintained.
- B37. The Applicant is required to enter a Works Authorisation Deed (WAD) with Transport for NSW for the proposed Bike Box on Western Avenue south approach to the Parramatta Road signalised intersection. Prior to the release of approved plans by TfNSW, the Applicant must submit a plan checking fee and lodge a performance bond in accordance with TfNSW requirements.

TfNSW – Civil Works

- B38. Detailed design plans and hydraulic calculations of any changes to the stormwater drainage system on Parramatta Road are to be submitted to TfNSW for approval, prior to the commencement of works (sending all documentation to development.sydney@transport.nsw.gov.au).
- B39. If the depth of excavation is greater than the linear distance from the state road reserve/property boundary, then the Applicant is to submit design drawings and documents relating to the excavation of the site and support structures to TfNSW for assessment, in accordance with Technical Direction GTD2020/001. The Applicant is to submit all documentation at least six weeks prior to the commencement of construction and is to meet the full cost of the assessment

by TfNSW. If it is necessary to excavate below the level of the base of the footings of the adjoining roadways, the person acting on the consent shall ensure that the owner/s of the roadway is/are given at least seven day notice of the intention to excavate below the base of the footings. The notice is to include complete details of the work.

- B40. Any proposed public utility adjustment/relocation works on the state road network will require detailed civil design plans for road opening/underboring to be submitted to TfNSW for review and acceptance prior to the commencement of works. The Applicant must also obtain any necessary approvals from the various public utility authorities and/or their agents.
- B41. The Applicant is required to enter a separate Works Authorisation Deed (WAD) with TfNSW for the works outlined in Conditions B37, B38 and B39 (where applicable). Prior to the release of approved plans by TfNSW, the Applicant must submit a plan checking fee and lodge a performance bond in accordance with TfNSW's standard requirements.

PART C DURING CONSTRUCTION

Site Notice

- C1. A site notice(s) must be prominently displayed at the boundaries of the site during construction for the purpose of informing the public of project details and must satisfy the following requirements:
- (a) minimum dimensions of the site notice(s) must measure 841 mm x 594 mm (A1) with any text on the site notice(s) to be a minimum of 30-point type size;
 - (b) the site notice(s) must be durable and weatherproof and must be displayed throughout the works period;
 - (c) the approved hours of work, the name of the builder, Certifier, structural engineer, site/project manager, the responsible managing company (if any), its address and 24-hour contact phone number for any inquiries, including construction/ noise complaint must be displayed on the site notice(s); and
 - (d) the site notice(s) must be mounted at eye level on the perimeter hoardings/fencing and must state that unauthorised entry to the site is not permitted.

Operation of Plant and Equipment

- C2. All construction plant and equipment used on site must be maintained in a proper and efficient condition and operated in a proper and efficient manner.

Demolition

- C3. Demolition work must comply with the demolition work plans required by *Australian Standard AS 2601-2001 The demolition of structures* (Standards Australia, 2001) and endorsed by a suitably qualified person as required by condition B8.

Construction Hours

- C4. Construction, including the delivery of materials to and from the site, may only be carried out between the following hours:
- (a) between 7am and 6pm, Mondays to Fridays inclusive; and
 - (b) between 8am and 1pm, Saturdays.
- No work may be carried out on Sundays or public holidays.
- C5. Construction activities may be undertaken outside of the hours in condition C4 if required:
- (a) by the Police or a public authority for the delivery of vehicles, plant or materials; or
 - (b) in an emergency to avoid the loss of life, damage to property or to prevent environmental harm; or
 - (c) where the works are inaudible at the nearest sensitive receivers; or
 - (d) for the delivery, set-up and removal of construction cranes, where notice of the crane-related works is provided to the Planning Secretary and affected residents at least seven days prior to the works; or
 - (e) where a variation is approved in advance in writing by the Planning Secretary or her nominee if appropriate justification is provided for the works.
- C6. Notification of such construction activities as referenced in condition C5 must be given to affected residents before undertaking the activities or as soon as is practical afterwards.
- C7. Rock breaking, rock hammering, sheet piling, pile driving and similar activities may only be carried out between the following hours:
- (a) 9am to 12pm, Monday to Friday;
 - (b) 2pm to 5pm Monday to Friday; and
 - (c) 9am to 12pm, Saturday.

Implementation of Management Plans

- C8. The Applicant must carry out the construction of the development in accordance with the most recent version of the CEMP (including Sub-Plans).

Construction Traffic

- C9. All construction vehicles (excluding site personnel vehicles) are to be contained wholly within the site, except if located in an approved on-street work zone, and vehicles must enter the site or an approved on-street work zone before stopping.

Hoarding Requirements

- C10. The following hoarding requirements must be complied with:
- (a) no third-party advertising is permitted to be displayed on the subject hoarding/ fencing; and
 - (b) the construction site manager must be responsible for the removal of all graffiti from any construction hoardings or the like within the construction area within 48 hours of its application.

No Obstruction of Public Way

- C11. The public way (outside of any approved construction works zone) must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances.

Construction Noise Limits

- C12. The development must be constructed to achieve the construction noise management levels detailed in the *Interim Construction Noise Guideline* (DECC, 2009). All feasible and reasonable noise mitigation measures must be implemented and any activities that could exceed the construction noise management levels must be identified and managed in accordance with the management and mitigation measures identified in the approved Construction Noise and Vibration Management Plan.
- C13. The Applicant must ensure construction vehicles (including concrete agitator trucks) do not arrive at the site or surrounding residential precincts outside of the construction hours of work outlined under condition C4.
- C14. The Applicant must implement, where practicable and without compromising the safety of construction staff or members of the public, the use of 'quackers' to ensure noise impacts on surrounding noise sensitive receivers are minimised.

Vibration Criteria

- C15. Vibration caused by construction at any residence or structure outside the site must be limited to:
- (a) for structural damage, the latest version of *DIN 4150-3 (1992-02) Structural vibration - Effects of vibration on structures* (German Institute for Standardisation, 1999); and
 - (b) for human exposure, the acceptable vibration values set out in the *Environmental Noise Management Assessing Vibration: a technical guideline* (DEC, 2006) (as may be updated or replaced from time to time).
- C16. Vibratory compactors must not be used closer than 30 metres from residential buildings unless vibration monitoring confirms compliance with the vibration criteria specified in condition C15.
- C17. The limits in conditions C15 and C16 apply unless otherwise outlined in a Construction Noise and Vibration Management Plan, approved as part of the CEMP required by condition B12 of this consent.

Tree Protection

C18. For the duration of the construction works:

- (a) street trees must not be trimmed or removed unless it forms a part of this development consent or prior written approval from Council is obtained or is required in an emergency to avoid the loss of life or damage to property;
- (b) all trees on the site that are not approved for removal must be suitably protected during construction as per the recommendations of the Arboricultural Impact Assessment prepared by tree iQ, Revision C dated 26 August 2024; and
- (c) if access to the area within any protective barrier is required during the works, it must be carried out under the supervision of a qualified arborist. Alternative tree protection measures must be installed, as required. The removal of tree protection measures, following completion of the works, must be carried out under the supervision of a qualified arborist and must avoid both direct mechanical injury to the structure of the tree and soil compaction within the canopy or the limit of the former protective fencing, whichever is the greater.

Air Quality

C19. The Applicant must take all reasonable steps to minimise dust generated during all works authorised by this consent.

C20. During construction, the Applicant must ensure that:

- (a) activities are carried out in a manner that minimises dust including emission of windblown or traffic generated dust;
- (b) all trucks entering or leaving the site with loads have their loads covered;
- (c) trucks associated with the development do not track dirt onto the public road network;
- (d) public roads used by these trucks are kept clean; and
- (e) land stabilisation works are carried out progressively on site to minimise exposed surfaces.

Soil and Water

C21. All erosion and sediment control measures must be effectively implemented and maintained at or above design capacity for the duration of the construction works and until such time as all ground disturbed by the works have been stabilised and rehabilitated so that it no longer acts as a source of sediment. Erosion and sediment control techniques, as a minimum, are to be in accordance with the publication Managing Urban Stormwater: Soils & Construction (4th edition, Landcom, 2004) commonly referred to as the 'Blue Book'.

Imported Fill

C22. The Applicant must:

- (a) ensure that only VENM, ENM, or other material that meets the requirements of a relevant order and exemption issued by the EPA, is brought onto the site;
- (b) keep accurate records of the volume and type of fill to be used; and
- (c) make these records available to the Certifier and/or the Planning Secretary within seven days upon request.

Disposal of Seepage and Stormwater

C23. Adequate provisions must be made to collect and discharge stormwater drainage during construction. The prior written approval of Council must be obtained to connect or discharge site stormwater to Council's stormwater drainage system or street gutter.

Emergency Management

- C24. The Applicant must prepare and implement awareness training for employees and contractors, including locations of the assembly points and evacuation routes, for the duration of construction.

Stormwater Management System

- C25. Within three months of the commencement of construction, the Applicant must design an operational stormwater management system for the development and submit it to the Certifier for approval. The system must:
- (a) be designed by a suitably qualified and experienced person(s);
 - (b) be generally in accordance with the conceptual design in the Civil Engineering Drawings prepared by Robert Bird Group, Sheet Number C-011-XX-01-[A01] to C-007-XX-09-[A01] dated 14/10/2024;
 - (c) be in accordance with applicable Australian Standards; and
 - (d) ensure that the system capacity has been designed in accordance with *Australian Rainfall and Runoff* (Engineers Australia, 2016) and *Managing Urban Stormwater: Council Handbook* (EPA, 1997) guidelines.

Aboriginal Cultural Heritage

- C26. Construction must be undertaken in accordance with the recommendations of the Aboriginal Cultural Heritage A01 Ross Street Teaching & Learning Hub, prepared by Urbis, dated 22 October 2024.
- C27. All reasonable steps must be taken to avoid harm, modification, or other impact to Aboriginal objects except as authorised by this approval.
- C28. Works are to avoid harm where possible to natural soil profiles within areas of identified moderate archaeological potential as shown in Figure 23 of the *Aboriginal Cultural Assessment A01 Ross Street Teaching & Learning Hub*, prepared by Urbis, dated 22 October 2024.
- C29. The Registered Aboriginal Parties must be kept informed about the SSD. The Registered Aboriginal Parties must continue to be provided with the opportunity to be consulted about the Aboriginal cultural heritage management requirements of the SSD.

Unexpected Finds Protocol – Aboriginal Heritage

- C30. In the event that surface disturbance identifies a new Aboriginal object:
- (a) all works must halt in the immediate area to prevent any further impacts to the object(s);
 - (b) a suitably qualified archaeologist and the registered Aboriginal representatives must be contacted to determine the significance of the objects;
 - (c) the site is to be registered in the Aboriginal Heritage Information Management System (AHIMS) which is managed by Heritage NSW under the NSW Department of Climate Change, Energy, the Environment and Water and the management outcome for the site included in the information provided to AHIMS;
 - (d) the Applicant must consult with the Aboriginal community representatives, the archaeologists and Heritage NSW to develop and implement management strategies for all objects/sites; and
 - (e) works may only recommence with the written approval of the Planning Secretary.

Unexpected Finds Protocol – Historic Heritage

- C31. If any unexpected archaeological relics are uncovered during the work, then:
- (a) all works must cease immediately in that area and notice is to be given to Heritage NSW and the Planning Secretary;
 - (b) depending on the possible significance of the relics, an archaeological assessment and management strategy may be required before further works can continue in that area as determined in consultation with Heritage NSW; and

- (c) works may only recommence with the written approval of the Planning Secretary.

Waste Storage and Processing

- C32. All waste generated during construction must be secured and maintained within designated waste storage areas at all times and must not leave the site onto neighbouring public or private properties.
- C33. All waste generated during construction must be assessed, classified and managed in accordance with the Waste Classification Guidelines Part 1: Classifying Waste (EPA, 2014).
- C34. The Applicant must ensure that concrete waste and rinse water are not disposed of on the site and are prevented from entering any natural or artificial watercourse.
- C35. The Applicant must record the quantities of each waste type generated during construction and the proposed reuse, recycling and disposal locations for the duration of construction.
- C36. The Applicant must ensure that the removal of hazardous materials, particularly the method of containment and control of emission of fibres to the air, and disposal at an approved waste disposal facility is in accordance with the requirements of the relevant legislation, codes, standards and guidelines.

Outdoor Lighting

- C37. The Applicant must ensure that all external lighting is constructed and maintained in accordance with AS 4282-2019 Control of the obtrusive effects of outdoor lighting.

Site Contamination

- C38. Prior to the commencement of any work that would result in the disturbance of potential or contaminated soils, materials, groundwater or sediments, the Applicant must conduct site investigations to confirm the full nature and extent of the contamination at the project area and comply with the following requirements:
- (a) the site investigations must be undertaken, and the subsequent report(s), must be prepared in accordance with relevant guidelines made or approved by the EPA under section 105 of the *Contaminated Land Management Act 1997*;
 - (b) the reports must be prepared, or reviewed and approved, by consultants certified under either the Environment Institute of Australia and New Zealand's Certified Environmental Practitioner (Site Contamination) scheme (CEnvP(SC)) or the Soil Science Australia Certified Professional Soil Scientist Contaminated Site Assessment and Management (CPSS CSAM) scheme; and
 - (c) the recommendations of the Remediation Action Plan prepared by Douglas Partners dated 22 August 2024.
- C39. The unexpected finds procedure within the Remediation Action Plan prepared by Douglas Partners dated 22 August 2024 must be updated following results of further site investigations undertaken in accordance with condition C38 and implemented throughout duration of project work.
- C40. Remediation of the site must be carried out in accordance with the Remediation Action Plan prepared by Douglas Partners and dated August 2024 and any variations to the Remediation Action Plan must be approved by an NSW EPA-accredited Site Auditor.
- C41. Where remediation is carried out / completed in stages, a NSW EPA-accredited Site Auditor must confirm satisfactory completion of each stage by the issuance of Interim Audit Advice(s).
- C42. The Applicant must ensure the proposed development does not result in a change of risk in relation to any pre-existing contamination on the site that would result in significant contamination.

Independent Environmental Audit

- C43. Independent Audits of the development must be conducted and carried out in accordance with the Independent Audit Post Approval Requirements.

- C44. Proposed independent auditors must be agreed to in writing by the Planning Secretary prior to the commencement of an Independent Audit.
- C45. The Planning Secretary may require the initial and subsequent Independent Audits to be undertaken at different times to those specified in the Independent Audit Post Approval Requirements, upon giving at least 4 week's notice (or timing) to the Applicant of the date upon which the audit must be commenced.
- C46. In accordance with the specific requirements in the Independent Audit Post Approval Requirements, the Applicant must:
- (a) review and respond to each Independent Audit Report prepared under condition C43 of this consent, or condition C48 where notice is given by the Planning Secretary;
 - (b) submit the response to the Planning Secretary; and
 - (c) make each Independent Audit Report, and response to it, publicly available within 60 days of submission to the Planning Secretary, unless otherwise agree by the Planning Secretary.
- C47. Independent Audit Reports and the Applicant's response to audit findings must be submitted to the Planning Secretary within two months of undertaking the independent audit site inspection as outlined in the Independent Audit Post Approval Requirements unless otherwise agreed by the Planning Secretary.
- C48. Notwithstanding the requirements of the Independent Audit Post Approval Requirements, the Planning Secretary may approve a request for ongoing independent operational audits to be ceased, where it has been demonstrated to the Planning Secretary's satisfaction that an audit has demonstrated operational compliance.

TfNSW – Road Occupancy License

- C49. A Road Occupancy Licence (ROL) shall be obtained from Transport Management Centre (TMC) for any works that may impact on traffic flows on Parramatta Road during construction activities. A ROL can be obtained through <https://myrta.com/oplinc2/pages/security/oplinclLogin.js>.

PART D PRIOR TO COMMENCEMENT OF OPERATION

Notification of Occupation

- D1. At least one month before commencement of any operation, the date of commencement of the operation of the development must be notified to the Planning Secretary in writing. If the operation of the development is to be staged, the Planning Secretary must be notified in writing at least one month before the commencement of each stage, of the date of commencement and the development to be carried out in that stage.

External Walls and Cladding

- D2. Prior to commencement of operation, the Applicant must provide the Certifier with documented evidence that the products and systems used in the construction of external walls including finishes and claddings such as synthetic or aluminium composite panels comply with the requirements of the BCA.
- D3. A copy of the documentation given to the Certifier must be made available on the Applicant's website within seven days after the Certifier accepts it.

Works as Executed Plans

- D4. Prior to the commencement of operation, works-as-executed plans signed by a registered surveyor demonstrating that the stormwater drainage and finished ground levels have been constructed as approved, must be submitted to the Certifier.

Outdoor Lighting

- D5. Prior to the commencement of operation, the Applicant must submit evidence from a suitably qualified practitioner to the Certifier that demonstrates that installed lighting associated with the development achieves the objective of minimising light spillage to any adjoining or adjacent sensitive receivers and:
- (a) complies with the latest version of AS 4282-2019 - *Control of the obtrusive effects of outdoor lighting* (Standards Australia, 1997); and
 - (b) has been mounted, screened and directed in such a manner that it does not create a nuisance to surrounding properties or the public road network.

Mechanical Ventilation

- D6. Prior to commencement of operation, the Applicant must provide evidence to the Certifier that the installation and performance of the mechanical ventilation systems complies with:
- (a) *AS 1668.2-2012 The use of air-conditioning in buildings – Mechanical ventilation in buildings* and other relevant codes; and
 - (b) any dispensation granted by Fire and Rescue NSW.

Operational Noise – Design of Mechanical Plant and Equipment

- D7. Prior to the commencement of operation, the Applicant must submit evidence to the Certifier that the noise mitigation recommendations in the assessment undertaken under condition B23 have been incorporated into the design of mechanical plant and equipment to ensure the development will not exceed the recommended operational noise levels identified in the SSDA Noise and Vibration Impact Assessment, prepared by Acoustic Logic, revision 2 dated 3/09/2024.

Fire Safety Certification

- D8. Prior to commencement of occupation, a Fire Safety Certificate must be obtained for all the Essential Fire or Other Safety Measures forming part of this consent. A copy of the Fire Safety Certificate must be submitted to the relevant authority and Council. The Fire Safety Certificate must be prominently displayed in the building.

Structural Inspection Certificate

- D9. Prior to the commencement of occupation of the relevant parts of any new or refurbished buildings, a Structural Inspection Certificate or a Compliance Certificate must be submitted to the Certifier. A copy of the Certificate with an electronic set of final drawings (contact approval

authority for specific electronic format) must be submitted to the Planning Secretary and the Council after:

- (a) the site has been periodically inspected and the Certifier is satisfied that the structural works is deemed to comply with the final design drawings; and
- (b) the drawings listed on the Inspection Certificate have been checked with those listed on the final Design Certificate/s.

Post-construction Dilapidation Report – Protection of Public Infrastructure

D10. Prior to the commencement of operation, the Applicant must engage a suitably qualified and experienced expert to prepare a Post-Construction Dilapidation Report. This Report must:

- (a) ascertain whether the construction works created any structural damage to public infrastructure by comparing the results of the Post-Construction Dilapidation Report with the Pre-Construction Dilapidation Report required by condition B5 of this consent;
- (b) have, if it is decided that there is no structural damage to public infrastructure, the written confirmation from the relevant public authority that there is no adverse structural damage to their infrastructure (including roads).
- (c) be submitted to the Certifier;
- (d) be forwarded to Council for information; and
- (e) be provided to the Planning Secretary within 48 hours when requested.

Repair of Public Infrastructure

D11. Unless the Applicant and the relevant public authority agree otherwise, the Applicant must:

- (a) repair, or pay the full costs associated with repairing, any public infrastructure that is damaged by carrying out the construction works; and/or
- (b) relocate, or pay the full costs associated with relocating any infrastructure that needs to be relocated as a result of the development; and/or
- (c) pay compensation for the damage as agreed with the owner of the public infrastructure.

Note: This condition does not apply to any damage to roads caused as a result of general road usage or otherwise addressed by contributions of this consent.

Road Damage

D12. Prior to the commencement of operation, the cost of repairing any damage caused to Council or other Public Authority's assets in the vicinity of the Subject Site as a result of construction works associated with the approved development must be met in full by the Applicant.

Utilities and Services

D13. Prior to commencement of operation, the Applicant must obtain a Compliance Certificate for water and sewerage infrastructure servicing of the site under section 73 of the *Sydney Water Act 1994*.

Stormwater Operation and Maintenance Plan

D14. Prior to the commencement of operation, a Stormwater Operation and Maintenance Plan (SOMP) is to be submitted to the Certifier. The SOMP must ensure the proposed stormwater quality measures remain effective and contain the following:

- (a) maintenance schedule of all stormwater quality treatment devices;
- (b) record and reporting details;
- (c) relevant contact information; and
- (d) Work Health and Safety requirements.

Operational Waste Management Plan

D15. Prior to the commencement of operation, the Applicant must prepare a Waste Management Plan for the development and submit it to the Certifier. The Waste Management Plan must:

- (a) detail the type and quantity of waste to be generated during operation of the development;

- (b) describe the handling, storage and disposal of all waste streams generated on site, consistent with the *Protection of the Environment Operations Act 1997*, *Protection of the Environment Operations (Waste) Regulation 2014* and the *Waste Classification Guideline* (Department of Environment, Climate Change and Water, 2009);
- (c) detail the materials to be reused or recycled, either on or off site; and
- (d) include the Management and Mitigation Measures included in the RtS.

Site Contamination

- D16. Prior to commencement of operation, the Applicant must submit a Validation Report for the development to the Certifier. The Validation Report must:
- (a) be prepared, or reviewed and approved, by consultants certified under either the Environment Institute of Australia and New Zealand's Certified Environmental Practitioner (Site Contamination) scheme (CEnvP(SC)) or the Soil Science Australia Certified Professional Soil Scientist Contate Assessment and Management (CPSS CSAM) scheme;
 - (b) be prepared in accordance with the relevant guidelines made or approved by the EPA under section 105 of the *Contaminated Land Management Act 1997*;
 - (c) include, but not be limited to:
 - (i) comment on the extent and nature of the remediation undertaken;
 - (ii) if material is to remain in-situ and capped, describe the location, nature and extent of any remaining contamination on site as well as any ongoing management requirements;
 - (iii) sampling and analysis plan and sampling methodology undertaken as part of the remediation;
 - (iv) if treated material is to remain on the subject site, results of sampling of treated material, compared with the treatment criteria in the most updated RAP;
 - (v) results of any validation sampling, compared to relevant guidelines/criteria;
 - (vi) comment on the suitability of the area for the intended land use; and
 - (d) be submitted to the Planning Secretary within 48 hours when requested.
- D17. Prior to commencement of operation, the Applicant must obtain confirmation from the Certifier in writing that the requirements of condition D16 have been met.
- D18. Where changes are made to the Remediation Action Plan under condition C38, prior to the commencement of operation, the Applicant must submit a Section A1 Site Audit Statement or a Section A2 Site Audit Statement accompanied by an Environmental Management Plan prepared by a NSW EPA accredited Site Auditor. The Section A1 or A2 Site Audit Statement must verify the relevant part of the site is suitable for the intended land use and be provided, along with any Environmental Management Plan to the Planning Secretary and the Certifier.

Landscaping

- D19. Prior to the commencement of operation, landscaping of the site must be completed generally in accordance with the landscape plan(s) listed in condition A2(d).
- D20. Prior to the commencement of operation, the Applicant must prepare a Landscape Management Plan to manage the landscaping on-site and submit it to the Certifier.

Green Travel Plan

- D21. Prior to commencement of operation, or other timeframe agreed in writing by the Planning Secretary, the Applicant must implement measures to promote the use of active and sustainable transport modes, as outlined in the Green Travel Plan (GTP) section in the Transport Impact Assessment, prepared by SCT Consulting, dated 13 February 2025, or the University's revised Sustainable Transport Access Management Plan (STAMP), whichever is the later.

Flood management – Engineering Certification/Validation

- D22. Prior to the commencement of operation, a Structural Inspection Certificate or other form of written certification from a suitable qualified civil or structural engineer must be submitted to the Certifier which certifies that the constructed building meets the requirements of condition B22.
- D23. The evidence required under condition D22 is to be made available to the Planning Secretary within seven days upon request.

Medium Rigid Vehicle (MRV) Movement Restriction

- D24. Prior to the commencement of operation, a sign 'No left turn, vehicles under 6m excepted' must be implemented for the left turn movement from Parramatta Road into Western Avenue. This sign (no left turn, vehicles under 6m excepted) is to be installed under 'Works Instruction' from TfNSW.

Affordable housing contribution

- D25. In accordance with the City of Sydney Affordable Housing Program and prior to the commencement of operation, the Applicant must provide evidence to the Certifier that a monetary contribution towards the provision of affordable housing has been paid to the City of Sydney Council, in accordance with the following:
- (a) The contribution is calculated by establishing the sum of the equivalent monetary contribution \$11,646.80 multiplied by 1% of the total floor area for non-residential development. The contribution is indexed at 1 March 2025.
 - (b) Plans detailing the total floor area must be submitted to the satisfaction of Council to determine the applicable contribution, where *total floor area* is defined under clause 7.13(6) of the Sydney Local Environmental Plan 2012.
 - (c) If the contribution is paid after the indexation period in which the consent is granted, 1 March 2025 to 28 February 2026, the above contribution will be adjusted according to the Sydney LGA median strata dwelling price ('MDP') using the following formula.
 - (d) Contribution payable at Time of Payment = $C \times MDP2 / MDP1$, where:
 - (i) C is the original total contribution amount payable to the City of Sydney as shown above;
 - (ii) MDP2 is the Median Strata Dwelling Price in Sydney LGA taken from the most recent NSW Government Rent and Sales Report at the time of indexation of the equivalent monetary contribution rate; and
 - (iii) MDP1 is the Median Strata Dwelling Price in Sydney LGA taken from the NSW Government Rent and Sales Report used to establish the current equivalent monetary contribution rate, being 1 March 2025 to 28 February 2026.

Note: Contact Council's Planning Assessment Unit at planningsystemsadmin@cityofsydney.nsw.gov.au for written confirmation of the amount payable, with indexation as necessary, prior to payment.

PART E POST OCCUPATION

Operation of Plant and Equipment

- E1. All plant and equipment used on site must be maintained in a proper and efficient condition operated in a proper and efficient manner.

Operational Noise Limits

- E2. The Applicant must ensure that noise generated by operation of the development does not exceed the noise limits in the SSDA Noise and Vibration Impact Assessment prepared by Acoustic Logic, version 3 dated 3/09/2024.

Ecologically Sustainable Development

- E3. Unless otherwise agreed by the Planning Secretary, within six months of commencement of operation, Green Star certification must be obtained demonstrating the development achieves a minimum 5 star Green Star Design & As Built rating. If required to be obtained, evidence of the certification must be provided to the Certifier and the Planning Secretary. If an alternative certification process has been agreed to by the Planning Secretary under condition B6, evidence of compliance of implementation must be provided to the Planning Secretary and Certifier.

Outdoor Lighting

- E4. External Lighting must comply with AS/NZS 4282:2023 Control of the Obtrusive Effects of Outdoor Lighting. Upon installation of lighting, but before it is finally commissioned, the Applicant must submit to the Certifier evidence from an appropriately qualified practitioner demonstrating compliance with this standard.
- E5. Notwithstanding condition E4, should outdoor lighting result in any residual impacts on the amenity of surrounding sensitive receivers, the Applicant must provide mitigation measures in consultation with affected landowners to reduce the impacts to a level acceptable to those landowners.

Landscaping

- E6. The Applicant must maintain the landscaping and vegetation on the site generally in accordance with the approved Landscape Management Plan required by condition D20 for the duration of occupation of the development.

Discharge Limits

- E7. The development must comply with section 120 of the POEO Act, which prohibits the pollution of waters.

Signage

- E8. All signage approved under this consent must be continuously maintained in a structurally sound and tidy manner by the Applicant for the duration of the development.

Use of Loading dock

- E9. All service vehicles accessing the loading bay must do so, wherever possible, outside of regular University teaching hours to minimise risks to pedestrians.

Flood information

- E10. Induction information for students and staff regarding flood hazards must be provided. This must include details of:
- (a) the flood emergency responses for operational phase of the development;
 - (b) hazards on local roads and live traffic information for road closures;
 - (c) predicted flood levels;
 - (d) flood warning time and flood notification;
 - (e) assembly points and evacuation routes; and
 - (f) evacuation and refuge protocols.

APPENDIX 1 ADVISORY NOTES

General

AN1. All licences, permits, approvals and consents as required by law must be obtained and maintained as required for the development. No condition of this consent removes any obligation to obtain, renew or comply with such licences, permits, approvals and consents.

Long Service Levy

AN2. For work costing \$250,000 or more, a Long Service Levy must be paid. For further information please contact the Long Service Corporation on 131 441.

Legal Notices

AN3. Any advice or notice to the consent authority must be served on the Planning Secretary.

Access for People with Disabilities

AN4. The works that are the subject of this application must be designed and constructed to provide access and facilities for people with a disability in accordance with the BCA. Prior to the commencement of construction, the Certifier must ensure that evidence of compliance with this condition from an appropriately qualified person is provided and that the requirements are referenced on any certified plans.

Utilities and Services

AN5. Prior to the construction of any utility works associated with the development, the Applicant must obtain relevant approvals from service providers.

AN6. Prior to the commencement of above ground works written advice must be obtained from the electricity supply authority, an approved telecommunications carrier and an approved gas carrier (where relevant) stating that satisfactory arrangements have been made to ensure provisions of adequate services.

Road Design and Traffic Facilities

AN7. All roads and traffic facilities must be designed to meet the requirements of Council or TfNSW (whichever is applicable). The necessary permits and approvals from the relevant road authority must be obtained prior to the commencement of road or pavement construction works.

Road Occupancy Licence

AN8. A Road Occupancy Licence must be obtained from the relevant road authority for any works that impact on traffic flows during construction activities.

SafeWork Requirements

AN9. To protect the safety of work personnel and the public, the work site must be adequately secured to prevent access by unauthorised personnel, and work must be conducted at all times in accordance with relevant SafeWork requirements.

Hoarding Requirements

AN10. The Applicant must submit a hoarding application to Council for the installation of any hoardings over Council footways or road reserve.

Handling of Asbestos

AN11. The Applicant must consult with SafeWork NSW concerning the handling of any asbestos waste that may be encountered during construction. The requirements of the Protection of the Environment Operations (Waste) Regulation 2014 with particular reference to Part 7 – 'Transportation and management of asbestos waste' must also be complied with.

Fire Safety Certificate

AN12. The owner must submit to Council an Annual Fire Safety Statement, each 12 months after the final Safety Certificate is issued. The certificate must be on, or to the effect of, Council's Fire Safety Statement.

APPENDIX 2 WRITTEN INCIDENT NOTIFICATION AND REPORTING REQUIREMENTS

Written Incident Notification Requirements

1. A written incident notification addressing the requirements set out below must be emailed to the Planning Secretary through the major projects portal within seven days after the Applicant becomes aware of an incident. Notification is required to be given under this condition even if the Applicant fails to give the notification required under condition A25 or, having given such notification, subsequently forms the view that an incident has not occurred.
2. Written notification of an incident must:
 - (a) identify the development and application number;
 - (b) provide details of the incident (date, time, location, a brief description of what occurred and why it is classified as an incident);
 - (c) identify how the incident was detected;
 - (d) identify when the Applicant became aware of the incident;
 - (e) identify any actual or potential non-compliance with conditions of consent;
 - (f) describe what immediate steps were taken in relation to the incident;
 - (g) identify further action(s) that will be taken in relation to the incident; and
 - (h) identify a project contact for further communication regarding the incident.
3. Within 30 days of the date on which the incident occurred or as otherwise agreed to by the Planning Secretary, the Applicant must provide the Planning Secretary and any relevant public authorities (as determined by the Planning Secretary) with a detailed report on the incident addressing all requirements below, and such further reports as may be requested.
4. The Incident Report must include:
 - (a) a summary of the incident;
 - (b) outcomes of an incident investigation, including identification of the cause of the incident;
 - (c) details of the corrective and preventative actions that have been, or will be, implemented to address the incident and prevent recurrence; and
 - (d) details of any communication with other stakeholders regarding the incident.